

#### SOP-GEN-032 500 Meter Zone and SIMOPS

- 1.0 Entering a Restricted Area
- 2.0 500m Entry Zone Protocol
- 3.0 Simultaneous Operations (SIMOPS)

Appendix A - 500M Checklist

### 1.0 Entering a Restricted Area

Based on the nature of work TDI-Brooks' vessels conduct, it is highly possible that it will need to enter an oil field, come within 500 m of a fixed structure or other restricted area. Basic guidelines include notifying the appropriate authorities (e.g., rig supervisor, offshore installation manager, marine operations manager etc.) to report vessel identification, estimated time of arrival, scope of work and proximity to restricted areas.

Do not enter a restricted area without permission and notification to all vessels or structures potentially impacted by this vessel's operations. It is imperative to maintain communications with all other vessels in vicinity, structures and points of notification to avoid any adverse impacts.

# 2.0 500 M Entry Zone Protocol

Prior to entering the 500-meter (m) zone of any offshore installation or floating structure, the Captain will contact the structure for permission and preferred approach protocols. At least **two qualified personnel** will be on the bridge during operations within the 500m Zone. Our basic protocol is described below but will be modified as required by structure/installation.

Some clients prefer that we use their form.

- The vessel establishes contact with the installation, provides an ETA.
- The vessel must ensure that they are familiar with the working practices of the installation, particularly the following: VHF/UHF working channels, communication contact points, physical layout of the installation, confirm with the installation vessel mooring requirements and method of mooring.
- Prior to arrival at the installation the vessel should confirm the satisfactory operation of all propulsion and maneuvering control equipment, steering

Title of Document:	Safety Management Manual	<b>Document Number:</b>	SOP-GEN-032	
Authority:	Director of Marine Operations	Revision:	2	
Custodian/Owner:	Designated Person Ashore	Issue Date:	May 2022	
			Page <b>1</b> of <b>4</b>	



control equipment, internal and external communication equipment, notify the installation of any cargo movement or needed assistance.

- Any problems need to be reported to the installation immediately.
- If conditions are acceptable, then the Captain needs to request permission to come alongside the installation.
- Once permission has been granted by the installation for approach, the Captain needs to establish and maintain contact with the installation, the vessel will be placed in the proper position that has been agreed to by the installation.
- At the installation, the following items need to be monitored: weather, wind, currents, VHF channel 16 and designated channel determined by both parties, distance to installation, condition and position of mooring lines, condition and position of any bulk hoses that may be connected to the vessel.
- Prior to departure, request permission from the installation, remove mooring lines, maintain contact with the installation until the vessel is outside of the 500 m zone.

Vessel is to confirm that all standby generators are online / running / available in the event of a black out. This will include having a manned engine room while inside the 500m Zone.

## 3.0 Simultaneous Operations (SIMOPS)

Should there be an occasion that more than one operation is being conducted off the vessel or an interaction between this vessel and another vessel or fixed platform structure, a SIMOPS plan will be developed to examine procedures, risks, mitigating factors and communication structure prior to commencing the activity. All concerned parties must stop and develop a SIMOPS to consider the issues prior to beginning work effort.

The Captain or Chief Mate of this vessel will be located on the vessel during all operations. The primary responsibility of the Captain is for the safety of the vessel and crew and pollution prevention. The Captain will be responsible for coordinating the activities of the vessel with any other vessels, seismic vessel, platforms and other facilities within the proposed work area.

Potential hazards to be considered in SIMOPS include:

Title of Document:	Safety Management Manual	Document Number:	SOP-GEN-032	
Authority:	Director of Marine Operations	Revision:	2	
Custodian/Owner:	Designated Person Ashore	Issue Date:	May 2022	
	Page <b>2</b> of <b>4</b>			



- Collision of vessels with fixed structures (including platforms) and other vessels, including seismic vessel.
- Entanglement of over-the-side equipment with fixed structures, other vessels and pipelines.
- Loss of over-the-side equipment.
- At sea transfers of supplies, personnel and fuel.
- Environmental impacts.

[Continued on next page]

Title of Document:	Safety Management Manual	<b>Document Number:</b>	SOP-GEN-032	
Authority:	Director of Marine Operations	Revision:	2	
Custodian/Owner:	Designated Person Ashore	Issue Date:	May 2022	
			Page <b>3</b> of <b>4</b>	



# Appendix A – 500m Checklist

Vessel Name:			Date:					
Installation Name:		Location		ocation (Field / Block):				
Side of Installation worked:		Installation heading:		ıg:				
VHF Installation:	Ch: VHF		HF (Crane/Deck):			Ch:		
<b>UHF Installation:</b>	СН:		UHF	IF (Crane/Deck)			СН:	
All specific marine hazards insi				essels l			37/4	
Approach/Anchoring positions es	stablished	Yes		No			N/A	
Anchor Chain Used (shots):		Wa	ter Dep					
Before Arrival	1 . 11	C 1		Yes	No	N/A	MANEUVERA	BILITY
Master and Watch keeping Mates sections of the SMS Manual.	s understand the content of the cont	of relev	vant				PROPULSION	
The weather conditions suitable f	for the proposed operation	ns					STEERING	
Two competent officers on bridge / Engine room manned (dependent upon ships manning)						BOW THR.		
Both generators running and on l	ine							
On arrival vessel to confirm			Yes	No	N/A	Comments		
Communications: VHF OR UHF sets / deck speakers and two-way comms. With deck foreman and crane tested.								
Assessment of prevailing conditions in 'set-up' position a minimum of 50 meters from the proposed working location has been performed.								
Radars set on standby								
Wearing of 'hi-vis' PPE by vesse	l deck crew whilst worki	ng alor	ngside.					
Internal and external Communications: VHF / UHF / Two-Way			Yes	No	N/A	Comments		
On vessel: Bridge, Deck and engine room communications.								
With installation: Control room, C	Crane and Deck commun	ication	ıs.					
Installation Radio Operator to confirm to the vessel:			Yes	No	N/A	Comments		
Whether the flare boom on the installation / rig is likely to be used.								
Confirm when operations are to commence.								
Permission to Enter 500MZ granted at: : Hrs. Checklist completed by:								
OFFLOADING OPERATIONS Yes No N/A Comments								
Follow the standard operating procedure for offloading the vessel. If needs be only one transfer operation at a time and that allows deviations from this procedure only after a formal risk assessment with both parties and the masters' / mate								
Once the job is complete, the master / mate to input information into the log book								
Permission to Depart granted at: : Hrs. Out of the 500MZ at: : Hrs.								

Title of Document:	Safety Management Manual	<b>Document Number:</b>	SOP-GEN-032	
Authority:	Director of Marine Operations	Revision:	2	
Custodian/Owner:	Designated Person Ashore	Issue Date:	May 2022	
			Page 4 of 4	